

**Colorado Department Of Transportation  
Notice To Contractors**

Printed On: **09/06/2022**

Read Order No. 001	Contract ID: <b>C20923RA</b>	Projects: NHPP0701-231
Letting Date: September 29, 10:00 AM	Contract UDBE Goal: 2.00 %	
Region: 3022	Guaranty: 5% of Total Bid	
Counties: MESA	For Plans and Specs go to <a href="http://cdot.dbesystem.com">http://cdot.dbesystem.com</a>	
	Fixed Completion Date: 3/24/2023	
	Res. 3410 Kaitlyn Codi Clark	970-683-6351

**Contract Description:**

THIS PROJECT IS LOCATED ON I-70 IN MESA COUNTY BEGINNING AT MM 18.46 AND EXTENDING WEST APPROXIMATELY 0.59 MILES TO MM 19.05. THE WORK FOR BRIDGES H-02-FM, H-02-FN, H-02-FO, AND H-02-FP CONSISTS OF CONSTRUCTION OF SCOUR COUNTERMEASURES INCLUDING:

1. DRILLING AND CONNECTING MICROPILES AT ABUTMENTS 1 AND 4 AND PIERS 2 AND 3.
2. PLACING RIPRAP AND GEOTEXTILE AT ABUTMENTS 1 AND 4 AND PIERS 2 AND 3.
3. REMOVING/REPLACING, AS REQUIRED, LOWER LITTLE SALT WASH RIVERFRONT TRAIL CONNECTION CONCRETE SIDEWALK.

SCHEDULE A CONSISTS OF ALL FOUR STRUCTURES

SCHEDULE B CONSISTS OF STRUCTURES H-02-FO AND H-02-FP AND GENERAL REPAIRS, DECK REPAIR, AND GUARDRAIL ON STRUCTURES H-02-FM AND H-02-FN

A MANDATORY PRE-BID CONFERENCE WILL BE HELD ON SEPTEMBER 13, 2022 AT 1:00 P.M. AT THE BOOKCLIFF CONFERENCE ROOM AT 2330 G ROAD, GRAND JUNCTION, COLORADO 81505 TO PRESENT A BRIEF OVERVIEW OF THE PROJECT AND TO ANSWER QUESTIONS FROM PROSPECTIVE BIDDERS. A MANDATORY PRE-BID SITE VISIT WILL FOLLOW THE CONFERENCE. BIDS WILL BE ACCEPTED ONLY FROM PRE-QUALIFIED BIDDERS WHO ATTEND THE MANDATORY PRE-BID CONFERENCE AND SITE VISIT.

Please register at [cdot.dbesystem.com](http://cdot.dbesystem.com) where plans and specs can be found in the "my bid solicitations" menu.

9/8/2022

One Publication: 9/8/2022

It is estimated that the total cost of all items in the bid will be:

- ( ) Between \$0 and \$1,000,000
- (X) Between \$1,000,000 and \$5,000,000
- ( ) Between \$5,000,000 and \$20,000,000
- ( ) Greater than \$20,000,000

Item No.	Description	Quantity	Units
	Major Items		
201-00000	Clearing and Grubbing	1.000	L S
202-00027	Removal of Riprap	218.000	SY
202-00504	Removal of Expansion Device	40.000	LF
203-00010	Unclassified Excavation (Complete In Place)	2,850.000	CY

Item No.	Description	Quantity	Units
	Major Items		
206-01781	Shoring (Area 1)	1.000	L S
206-01782	Shoring (Area 2)	1.000	L S
206-01783	Shoring (Area 3)	1.000	L S
206-01784	Shoring (Area 4)	1.000	L S
207-00700	Topsoil (Onsite)	3,896.000	CY
207-00704	Subgrade Soil Preparation	23,377.000	SY
208-00013	Erosion Log Type 1 (20 Inch)	2,755.000	LF
208-00070	Vehicle Tracking Pad	12.000	EACH
208-00075	Pre-fabricated Vehicle Tracking Pad	12.000	EACH
208-00207	Erosion Control Management	85.000	DAY
210-02900	Relay Riprap	156.000	CY
212-00701	Compost (Mechanically Applied)	314.000	CY
250-00010	Environmental Health and Safety Management	1.000	L S
304-06007	Aggregate Base Course (Class 6)	45.000	CY
503-01080	Micropile (8 Inch)	4,512.000	LF
503-02000	Verification Test Pile	2.000	EACH
506-00212	Riprap (12 Inch)	574.000	CY
601-03040	Concrete Class D (Bridge)	18.700	CY
601-06100	Concrete (Patching)	0.100	CY
602-00000	Reinforcing Steel	4,480.000	LB
606-00350	Guardrail Type 3 (Double) (6-3 Post Spacing)	300.000	LF
606-01460	Median Terminal	2.000	EACH
607-11525	Fence (Plastic)	3,225.000	LF
608-00000	Concrete Sidewalk	212.000	SY
608-00350	Concrete Sidewalk (Colored)	55.000	SY
620-00002	Field Office (Class 2)	1.000	EACH
621-00411	Structure Temporary Access Road (Location 1)	1.000	L S
621-00412	Structure Temporary Access Road (Location 2)	1.000	L S
625-00000	Construction Surveying	1.000	L S
625-00001	Construction Surveying (Hourly)	10.000	HOUR
626-00000	Mobilization	1.000	L S
626-01113	Public Information Management (Tier III)	144.000	DAY
630-00000	Flagging	1,700.000	HOUR
630-00012	Traffic Control Management	85.000	DAY
630-80377	Portable Water Filled Barrier (Temporary)	400.000	LF
630-85041	Mobile Attenuator	85.000	DAY